



How to upgrade NX510 tablet system after replacing a new tablet front shell

Introduction

After replacing a new tablet front shell, if it can not fit original tablet system, we need to update the system to a new version(HC_SPRING_A_V1.33_LCD7-10_W1B0_LPDDR_CN_MDM_20230417).

Prerequisites

Hardware: NX510SE tablet(PN with 4090040017 and 4090040018), U disk, wired mouse and a cell phone or computer that can provide remote assistance.Please refer to the below link to download the system file;

<https://chcnavigation.jianguoyun.com/p/DZqZ6c8Qwv2xCxjiiYMFIAA>

Software: NX510 tablet system

Steps

- 1) Wired Mouse for Tablet Connection as below.




- 2) Use mouse to start RemoteDesk or AnyDesk.



- 3) Unplug the wired mouse and Insert the U disk with the upgrade file. Control the tablet remotely using your computer or cell phone, following as below.


- a) Copy the system file into U disk and connect U disk to the tablet, then move the system file into [Home] path;




b) Go to [Update] option in the main interface;




c) Click the updates arrow in the middle of interface;




d) Click [Local update], then select the system file imported;



e) After verifying the system package, click [Start install];



f) After confirm the battery is above 90%, click [Ok] to install;





CHC Navigation

Building C, 577 Songying Road, Qingpu, District,
201702 Shanghai, China

Tel: +86 21 542 60 273 | Fax: +86 21 649 50 963

Email: sales@chcnav.com | support@chcnav.com

Skype: [chc_support](https://www.skype.com/people/chc_support)

Website: www.chcnav.com

Shanghai Huace Navigation Technology Ltd.
Building C, 577 Songying Road, Qingpu, District,
201702 Shanghai, China

WWW.CHCNAVCOM
Tel: +86 21 54260273
Stock Code:300627